

<b>5</b>	<b>INTERFERENCE.....</b>	<b>2</b>
<b>5.1</b>	<b>GENERAL.....</b>	<b>2</b>
5.1.1	Scope .....	2
<b>5.2</b>	<b>INTERFERENCE .....</b>	<b>2</b>
5.2.1	Land Interests.....	2
5.2.2	Existing Properties.....	2
5.2.3	Existing Roads.....	2
5.2.4	Apparatus .....	3

## 5 INTERFERENCE

### 5.1 GENERAL

#### 5.1.1 Scope

- 1 This Part specifies the requirements associated with interference with land interests, existing properties, existing roads and apparatus.
- 2 Related Sections and Parts are as follows:  
  
This Section  
Part 15..... Temporary Controls

### 5.2 INTERFERENCE

#### 5.2.1 Land Interests

- 1 The Contractor shall confine his construction operations within the Site, or such other area of land as may be negotiated, and shall instruct his employees not to trespass.
- 2 Subject to any unavoidable disturbance which may be necessitated by the execution of the Works, the Contractor shall not interfere with land use which may be enjoyed on or near the Site.
- 3 The Contractor shall notify the Engineer in writing of his intention to utilise any land outside the site and obtain the written approval of the Engineer before approaching any landowner for use of their land.
- 4 Before exercising any right negotiated by him in connection with using land outside the site, the Contractor shall notify the Engineer in writing of such arrangements. The details of the arrangements shall include drawing and description of the land to be used, purpose of its use and duration of the Contractor use of the land.

#### 5.2.2 Existing Properties

- 1 The Contractor shall obtain the approval of the Engineer before interfering with access to any property, and shall also obtain the approval of the Engineer to any alternative access arrangements.
- 2 The Contractor shall notify the Engineer and the relevant owners and occupiers in writing fourteen(14)days in advance of any such interference and shall confirm to the Engineer that the alternative arrangements have been agreed with the relevant owners and occupiers.

#### 5.2.3 Existing Roads

- 1 The Contractor shall take all reasonable steps to prevent vehicles entering and leaving the Site depositing mud or other debris on the surface of adjacent roads or footways, and shall remove any materials so deposited.
- 2 The Contractor shall be responsible for all damage to public or private roads or streets arising out of or by reason of the execution of the Works.
- 3 The Contractor shall not permit tracked vehicles to travel along permanent or temporary roads without the use of timber mats or other approved precautions to prevent damage.

- 4      The Contractors shall be held responsible for any damage caused by him, Contractor's Employees, sub-contractors or suppliers to public or private roads, paved areas, paths verges, trees, shrubs, fences, boundary walls, gates, signs, drains and buildings, ducts, and services arising out of or by reason of the execution of the Works and shall bear cost of making good any damage to the entire satisfaction of the local , other authorities and owners. The Contractor shall keep all private roads and paths clean and free from dirt and debris and any obstruction associated with the Works, which would prejudice the safe and unimpeded normal use of the said roads and paths.

**5.2.4    Apparatus**

- 1      The Contractor shall not obstruct access to any manhole or other surface access cover.

END OF PART