

2	SITE CLEARANCE	2
2.1	GENERAL SITE INSTALLATION AND SITE MANAGEMENT	2
2.1.1	General.....	2
2.1.2	Site Restrictions.....	2

ARAB ENGINEERING BUR

2 SITE CLEARANCE

2.1 GENERAL SITE INSTALLATION AND SITE MANAGEMENT

2.1.1 General

- 1 All project related works for site installation and site equipment shall be carried out according to QCS Section 1.

2.1.2 Site Restrictions

- 1 The Contractor shall confine the work activities, including storage of construction materials, movement and packing of equipment, machinery and Contractor's Equipment within the allocated Works areas.
- 2 The Contractor shall execute his work in such a manner as to cause minimal inconvenience to the public and other contractors.
- 3 The Contractor shall fully control his workforce and those of his Subcontractors, to ensure that workers do not loiter in public areas or facilities and do not intimidate local residents.
- 4 Concrete batching and mixing plant, supplied as Contractor's Equipment and erected on the Site shall only be used for the Works.
- 5 Bituminous materials, batching and mixing plant, supplied as Contractor's Equipment and erected on the Site shall only be used for the Works.
- 6 Unless otherwise stated, the Contractor shall pay all rates and charges of any nature whatsoever arising out of his use of the Site and all Works areas provided therein under the Contract.

END OF PART